

**EXHIBIT C – CONSTRUCTION MITIGATION MEASURES****Construction Mitigation Measures:**

These measures have been adapted from sheet C101 in Exhibit D. Unless otherwise noted, please refer to sheet C101 for details. All mitigation measures mentioned on sheet C101 and not mentioned below either do not apply or the CCSD will manage compliance.

1. AES/MM-4: imported rocks used in drainage systems must match the color of the adjacent soil to the extent feasible.
2. AQ/M M-1: Contractor to prepare and submit to the APCD a dust control plan using BMP and dust mitigation measures.
3. AQ/MM-3: Contractor to comply with the provisions of this mitigation measure to reduce PM10 emissions. The building pad area and the area that will be paved will use chemical/soil binder dust control measures as outlined in item “e” if required by the APCD. All areas outside the building pad or paving shall use the seeding method outlined in item “d.”
4. AQ/MM-5: Does not apply.
5. BIO/MM-3: CCSD to comply with this measure.
6. GEO/MM-3: CCSD to comply with this measure.
7. GEO/MM-9: CCSD to comply with this measure.
8. HM/MM-4: CCSD to comply with this measure.
9. HYD/MM-2: Completed.
10. HYD/MM-3: Completed.
11. N/MM-2: Completed.
12. BIO/MM-2: CCSD to comply with this measure.
13. BIO/MM-14: CCSD to comply with this measure.
14. BIO/MM-17: CCSD to comply with this measure and provide training. All employees of Contractor working onsite must receive this training.
15. BIO/MM-25: CCSD to comply with this measure.
16. BIO/MM-26: CCSD to comply with this measure.
17. CULT/MM-3: CCSD to comply with this measure.
18. AES/MM-6: imported rocks used in drainage systems must match the color of the adjacent soil to the extent feasible.
19. AES/MM-9: Not applicable to this project.

## EXHIBIT C – CONSTRUCTION MITIGATION MEASURES

20. AQ/MM-2: to comply with this measure, the contractor must supply CCSD with a list of all heavy-duty construction equipment operating at the site. The list shall include the make, model, engine size, and year of each piece of equipment. This compliance review will identify all equipment and operations requiring permits and will assist in the identification of suitable equipment for the catalyzed diesel particulate filter; CCSD to apply for an authority to construct from the APCD using this information. This information must be supplied with the bid.
21. AQ/MM-4: N/A. Construction will not last more than one month.
22. BIO/MM-5: N/A. Work occurring more than 50 feet from a drainage.
23. BIO/MM-6: N/A
24. BIO/MM-7: Contractor to comply with vehicle and equipment checks, as well as spill prevention and cleanup provisions. The staging area will be on the gravel parking lot adjacent to the work area.
25. BIO/MM-8: N/A
26. BIO/MM-9: Measures from AQ/MM-3 will be used to comply.
27. BIO/MM-11: The area was previously disturbed; CCSD will perform a survey to confirm no applicable plants exist within the project area.
28. BIO/MM-12: The area was previously disturbed; CCSD will perform a survey to confirm no applicable plants exist within the project area. CCSD and the Contractor to work together to delineate the construction area to minimize impacts to the surrounding area.
29. BIO/MM-15: construction is outside the 100-foot zone.
30. BIO/MM-19: CCSD and contractor to work together to delineate the construction area. Access to the construction site will be via established gravel roadways.
31. BIO/MM-20: Contractor to remove all food-containing trash at the end of each workday or use sealing lids on trash cans containing food-related trash. Contractor to remove all trash and debris, including extra soil, generated from construction activities at the end of the project.
32. BIO/MM-21: Contractor to comply with this provision, except for those activities performed by the monitor. Refueling shall take place at the staging area in the gravel parking lot.
33. BIO/MM-22: Contractor to seed disturbed areas outside of building and pavement footprints. See AQ/MM-3.
34. BIO/MM-24: See Sheet C700 for erosion/sedimentation control plan.
35. CULT/MM-9: CCSD to comply.
36. GEO/MM-7: N/A
37. HYD/MM-1: N/A
38. N/MN-1: Construction equipment is limited to between 7 a.m. and 9 p.m. Monday through Friday and 8 a.m. and 5 p.m. Saturday and Sunday.
39. AES/MM-7: N/A
40. BIO/MM-27: N/A

**EXHIBIT C – CONSTRUCTION MITIGATION MEASURES**

41. CULT/MM-4: CCSD to comply.
42. CULT/MM-6: N/A
43. CULT/MM-8: CCSD to comply.
44. GEO/MM-1: N/A
45. GEO/MM-6: N/A
46. HM/MM-2: Smoking on the worksite is prohibited.
47. HM/MM-3: CCSD to comply,
57. No Landscaping to be installed. Disturbed areas not being built on or paved to be seeded with native grass; see AQ/MM-3.
58. CCSD to comply with all the On-going Conditions of Approval.

**-- END CONSTRUCTION MITIGATION MEASURES --**